

## PATENT COOPERATION TREATY

PCT

## NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

Assistant Commissioner for Patents  
United States Patent and Trademark  
Office  
Box PCT  
Washington, D.C.20231  
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 09 October 2000 (09.10.00)	
International application No. PCT/FI00/00025	Applicant's or agent's file reference 2990008PC/su
International filing date (day/month/year) 14 January 2000 (14.01.00)	Priority date (day/month/year) 15 January 1999 (15.01.99)
Applicant RÄSÄNEN, Juha et al	

1. The designated Office is hereby notified of its election made:

☒ in the demand filed with the International Preliminary Examining Authority on:

04 August 2000 (04.08.00)

☐ in a notice effecting later election filed with the International Bureau on:2. The election ☒ was☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland	Authorized officer Manu Berrod
Facsimile No.: (41-22) 740.14.35	Telephone No.: (41-22) 338.83.38




## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification <sup>7</sup> : <b>H04Q 7/24, 11/04</b>		<b>A1</b>	(11) International Publication Number: <b>WO 00/42792</b>
			(43) International Publication Date: 20 July 2000 (20.07.00)
(21) International Application Number: PCT/FI00/00025 (22) International Filing Date: 14 January 2000 (14.01.00) (30) Priority Data: 990071                      15 January 1999 (15.01.99)                      FI (71) Applicant (for all designated States except US): NOKIA NETWORKS OY [FI/FI]; Keilalahdentie 4, FIN-02150 Espoo (FI). (72) Inventors; and (75) Inventors/Applicants (for US only): RÄSÄNEN, Juha [FI/FI]; Pensaskertuntie 8 A, FIN-02660 Espoo (FI). OHVO, Mikko [FI/FI]; Johanbergintie 102, FIN-04660 Numminen (FI). (74) Agent: KOLSTER OY AB; Iso Roobertinkatu 23, P.O. Box 148, FIN-00121 Helsinki (FI).		(81) Designated States: AE, AL, AM, AT, AT (Utility model), AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, CZ (Utility model), DE, DE (Utility model), DK, DK (Utility model), DM, EE, EE (Utility model), ES, FI, FI (Utility model), GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KR (Utility model), KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SK (Utility model), SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).  Published With international search report. Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.	

(54) Title: FLOW CONTROL METHOD IN A TELECOMMUNICATIONS SYSTEM

## (57) Abstract

The invention relates to flow control in data transmission in telecommunications systems, particularly in wireless telecommunications systems. In the present invention flow control information is tunnelled over a connection leg (lu) which does not support flow control on a lower transmission protocol layer (ATM) underlying a user level (LAC). The nodes (RNC, 3G MSC) at the both ends of the leg (lu) are arranged to use the flow



control information to control the data flow on the lower transmission protocol level (ATM) of the leg. In other words, the transmission of new data on the lower transmission protocol level (ATM) is ceased or the data rate decreased when the flow control information activates the flow control in the transmitting node, and similarly, the transmission of new data on the lower transmission protocol level (ATM) is restarted or the data rate increased when the conveyed flow control information deactivates the flow control. The need of flow control may be recognized from the receiving buffer status on the lower transmission protocol level or from incoming flow control information received over the following leg of the connection in the downlink direction.

**FOR THE PURPOSES OF INFORMATION ONLY**

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece	ML	Mali	TR	Turkey
BG	Bulgaria	HU	Hungary	MN	Mongolia	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MR	Mauritania	UA	Ukraine
BR	Brazil	IL	Israel	MW	Malawi	UG	Uganda
BY	Belarus	IS	Iceland	MX	Mexico	US	United States of America
CA	Canada	IT	Italy	NE	Niger	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NL	Netherlands	VN	Viet Nam
CG	Congo	KE	Kenya	NO	Norway	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NZ	New Zealand	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	PL	Poland		
CM	Cameroon	KR	Republic of Korea	PT	Portugal		
CN	China	KZ	Kazakstan	RO	Romania		
CU	Cuba	LC	Saint Lucia	RU	Russian Federation		
CZ	Czech Republic	LI	Liechtenstein	SD	Sudan		
DE	Germany	LK	Sri Lanka	SE	Sweden		
DK	Denmark	LR	Liberia	SG	Singapore		
EE	Estonia						

## Flow control method in a telecommunications system

### Field of the Invention

The invention relates to flow control in data transmission in telecommunications systems, particularly in wireless telecommunications systems.

### 5 Background of the Invention

Wireless communications systems refer generally to any telecommunications system which enables wireless communication between the users and the network. In mobile communications systems users are capable of moving within the service area of the system. A typical mobile communications  
10 system is a public land mobile network (PLMN).

The present third generation mobile systems, such as Universal Mobile Communications system (UMTS) and Future Public Land Mobile Telecommunications system (FPLMTS), later renamed as IMT-2000 (International Mobile Telecommunication 2000), are being developed. The UMTS is being  
15 standardized in the ETSI (European Telecommunication Standards Institute) whereas the ITU (International Telecommunication Union) is defining the IMT-2000 system. The radio interface is likely to be based on a wide band CDMA (Code Division Multiple Access), and therefore the third generation systems are often referred to as wide band CDMA systems (WCDMA). These future  
20 systems are basically very alike.

Figure 1 shows a simplified UMTS architecture with external reference points and interfaces to the UMTS terrestrial radio access network, UTRAN. The UTRAN consists of a set of radio access networks RAN (also called radio network subsystem RNS) connected to the core network (CN) through  
25 the interface Iu. These radio network subsystems can be interconnected together through an interconnection point (reference point) Iur. The interfaces Iu(s) and Iur are logical interfaces. The Iur can be converged over physical direct connection between RANs or via any suitable transport network. Each RAN is responsible for the resources of its set of cells. On each connection  
30 between a mobile station MS and the UTRAN, one RAN is a serving RAN. A RAN consists of a radio network controller RNC and a multiplicity of base stations BS. The RNC is responsible for the handover decisions that require signalling to the MS. The base stations are connected to the RNC through the Iub interface. The core network CN is a conventional or future telecommunications

network modified to efficiently utilize the UTRAN in wireless communication. Telecommunications networks that are thought to be suitable core networks include second generation mobile communications systems, such as GSM, and other telecommunications systems, such as ISDN (Integrated Services  
5 Digital Network), BISDN (Broadband ISDN), PDN (Packet Data Network), etc.

Transition to the use of third generation mobile systems will occur in steps. In the first step the 3G radio access network will be introduced into the 2G network infrastructure. Such a "hybrid system" is illustrated by the RNC1 connected to a 2GMSC10 in Fig.1. As the 3G radio access network will not be  
10 compatible to the 2GMSC, it is apparent that such a mixed architecture requires interworking between the 2G and the 3G elements. This interworking is typically depicted as an interworking unit (IWU), such as IWU11 in Fig. 1. The general requirement is that no modifications are allowed in the 2G system (in the 2GMSC), and thereby the interface between the 2MSC and the IWU must  
15 be a pure A interface according to the GSM specifications. Later the development will result in a situation where pure 3G mobile systems exist side by side with the 2G mobile systems or the hybrid systems. In Figure 1, the RNC2 and the third generation MSC12 illustrate a pure 3G system.

Figure 2 illustrates protocol stacks which may be employed in a  
20 pure 3G mobile system. A traffic channel (the user plane) layer between the mobile station MS and the RNC uses a radio link control (RLC) protocol and the medium access control (MAC). The RLC provides a radio-solution dependent on a reliable link over the radio path. It takes care of segmentation and assembly of the data from and to the upper layer before and after trans-  
25 mission over the radio path, respectively, as well as of retransmissions. Under the RLC the MAC function controls the mapping of the RLC protocol data units (RLC-PDUs) into physical channels in the physical layer. The physical layer includes all the schemes and mechanisms used to make communication possible on the radio channel. These mechanisms include, for example, modula-  
30 tion, power control, coding and timing. Wide band CDMA (WCDMA) and time division CDMA (TD-CDMA) are mentioned as examples of multiple access methods which can be used in the radio interface.

In the interface Iu between the radio network controller RNC and the mobile switching centre MSC or the IWU, a potential candidate for transfer  
35 technique is the ATM (Asynchronous Transfer Mode). The ATM transmission technique is a switching and multiplexing solution particularly related to a data

link layer (i.e. OSI layer 2, hereinafter referred to as an ATM layer). In the ATM data transmission the end users' data traffic is carried from a source to a destination through virtual connections. Data is transferred over switches of the network in standard-size packets called ATM cells. The ATM cell comprises a header, the main object of which is to identify a connection number for a sequence of cells forming a virtual channel for a particular call. A physical layer (i.e. OSI layer 1) may comprise several virtual paths multiplexed in the ATM layer. The ATM layer contains an ATM adaptation layer (AAL) which enhances the service provided by the ATM layer to support functions required by the next higher layer. The AAL performs functions required by the user and control and management planes and supports the mapping between the ATM layer and the next higher layer. The functions performed in the AAL depend upon the higher layer requirements. At the moment there are three different types of AAL, namely type 1 AAL (AAL1), type 2 AAL (AAL2) and type 5 AAL (AAL5).

A further retransmitting and error correcting protocol (LAC, Link Access Control) may or may not be specified to be used between the MS and the RNC or between the MS and the MSC (or the IWU), as shown in Figures 2 and 3. The LAC, if any, may be similar to the radio link protocol (RLP) employed in the GSM system. The circuit switched leg from the MSC to the fixed network uses standard PSTN or ISDN protocols (e.g. ISDN V.120) or possibly some other protocols on a dedicated connection.

Figure 3 illustrates protocol stacks in a hybrid system in which a 3G radio access is connected to a 2G MSC via an interworking unit (IWU). In this case the ATM connection is terminated in the IWU. The leg between the IWU and the 2G MSC uses standard GSM protocols (the interface A). The interface between the MS and the RNC as well as the interface Iu are between the RNC and the IWU are similar to those described with reference to Figure 1.

The data rates on the concatenated legs (e.g., MS-RNC, RNC-MSC, MSC-fixed network) may be different in a circuit switched data call. The legs may have different nominal rates due to the different capacity of the channels and/or various retransmission conditions may make the effective data rate of a leg lower than the nominal data rate. Retransmissions can take place both on the MS-RNC leg with the MAC/RLC protocol (and possibly with the LAC protocol) and on the MSC-fixed network leg with the V.120 protocol, for example. If the LAC is implemented between the MS and the MSC (or the IWU), retransmissions can take place on this leg too on a higher protocol level.

The MAC/RLC and LAC protocols and many fixed network protocols, such as V.120, have inherent flow control mechanisms. The flow control is used by a receiver at one end of the leg or connection to control the data transmission from a transmitter at the other end of the leg or connection.

5 When the receiver is not able to process e.g. forward the data at the same speed as it is received from the leg or connection, the receiving buffer starts to fill up. In such a situation the receiver may send a flow control ON request to the transmitter, which goes into a 'flow control active' mode. In the 'flow control active' mode the transmitter ceases the transmission of new data to the receiver or decreases the data rate. Moreover, in case of concatenated legs, the transmitting end may also activate the flow control in the previous leg in order to avoid the filling up of the receiving buffer since it is not able to forward the received data in the 'active flow control' mode. As a result, the overflow of receiving buffers and discarding of user data can be avoided in each leg of the

10 end-to-end connection and thereby over the whole end-to-end connection. As a result data integrity is also maintained.

However, no end-to-end connection related flow control is supported by the current ATM specifications. The ATM only supports flow control from the user to the network. If the flow control is active, the network discards

20 cells instead of sending them to the user. Another flow control mechanism supported by the ATM is based on the recognition of a congestion in the network; in case of congestion lower priority cells are discarded by the network. The discarding of data will deteriorate the data integrity.

The fact that the end-to-end flow control is not supported by the

25 ATM results in problems when the ATM is used in the interface Iu between the RNC and the 3GMSC or the IWU, as shown in Figures 2 and 3. More particularly, one leg along the end-to-end connection consisting of various concatenated legs does not support flow control, and therefore the end-to-end flow control fails. Let us study the situation more carefully with respect to Figures 2 and 3. In case there is no LAC over any of the legs or the LAC is operating between the MS and the RNC only, the current flow control mechanisms cannot guarantee data integrity in a circuit switched data call in the 3G mobile network using the ATM connection between the RNC and the MSC (or the IWU). The flow control activated towards the ATM leg does not stop sending

30 data from the sending entity but leads to an overflow of receiving buffers or to discarding of ATM cells carrying user data. In case the LAC is operating be-

tween the MS and the MSC (or the IWU), the current flow control mechanisms require a huge buffer (a whole LAC retransmission window) in the RNC to guarantee the data integrity in a circuit switched data call in the 3G network using the ATM connection between the RNC and the MSC (or the IWU). The flow control towards the ATM leg does not stop sending data from the sending entity but leads to an overflow of the receiving buffer or to discarding of ATM cells carrying user data. In the latter case the use of the huge buffer in order to maintain the integrity of the data is very impractical due to the memory requirements in the RNC. In any case this will not work at all if there is no LAC at all or the LAC operates only between the MS and the RNC.

A similar problem may be encountered in any telecommunications system in which one or more of the concatenated connection legs do not support flow control.

#### **Disclosure of the Invention**

An object of the invention is to overcome the above problems in the flow control in telecommunications systems.

An aspect of the present invention is a data transmission method in a telecommunications system, comprising the steps of

transmitting data over a connection comprising a first leg supporting flow control on a lower transmission protocol level underlying a user level, an intermediate second leg not supporting flow control on the lower transmission level, and a third leg supporting flow control on the lower transmission protocol level,

tunnelling lower level flow control information transparently over the lower transmission protocol level of the second leg between said first and third legs in order to provide end-to-end flow control and thereby data integrity over the connection on the lower transmission protocol layer.

Another aspect of the present invention is a telecommunications system, comprising

a first connection leg supporting flow control on a lower transmission protocol level underlying a user level,

an intermediate second connection leg not supporting flow control on the lower transmission level,

a third connection leg supporting flow control on the lower transmission protocol level,



a first node between the first and second legs,  
a second node between the second and third legs,  
the first and second nodes being arranged to tunnel lower level flow control information transparently over the lower transmission protocol level of the second leg between said first and third legs in order to provide end-to-end flow control and thereby data integrity over the connection on the lower transmission protocol layer.

In the present invention flow control information is tunnelled over the leg which does not support flow control on a lower transmission protocol layer underlying a user level. The nodes at the both ends of the leg are arranged to use the flow control information to control the data flow on the lower transmission protocol level of the leg. In other words, the transmission of new data on the lower transmission protocol level is ceased or the data rate is decreased when the flow control information activates the flow control in the transmitting node, and similarly, the transmission of new data on the lower transmission protocol level is restarted or the data rate is increased when the conveyed flow control information deactivates the flow control. The need of flow control may be recognized from the receiving buffer status on the lower transmission protocol level or from incoming flow control information received over the following leg of the connection in the downlink direction.

In order to implement the flow control, the flow control information may be employed by the user layer protocol entity. The user layer entity may implement the above flow control by controlling the data input from the user layer to the underlying lower transmission protocol layer, and/or by activating the flow control mechanism of the lower transmission protocol layer of the previous leg in the uplink direction, e.g. by mapping or converting the tunnelled flow control information into the flow control information according to the protocol of the next leg. In the latter case the lower layer protocol entity of the previous leg in the same node may stop forwarding new data to a leg not supporting the flow control, and/or the respective lower protocol entity at the far end of the previous leg may stop sending new data. In each case the data flow on the lower transmission protocol level of the leg not supporting the flow control can be controlled and the overflow of data buffers or discarding of data can be avoided in each leg of the end-to-end connection. As a result, the integrity of the data can be assured with the lower level flow control mechanisms only, without any need for high-level flow control. Also large buffers will be avoided.

The inventive concept also allows, however, the use of a high-level protocol, such as the LAC, in one of the legs of the connection or over the whole end-to-end connection.

5 The flow control information may be tunnelled over the leg not supporting the flow control as in-channel signalling or in out-channel signalling associated with a connection.

10 In the preferred embodiment of the invention the connection leg not supporting the flow control is an ATM connection, and the lower transmission protocol level includes an ATM adaptation layer. In order to implement the in-channel signalling embodiment, flow control information may be inserted into the ATM adaptation layer service data unit which is then transported over the leg not supporting the flow control to the other end in accordance with an ATM network protocol. At the other end the flow control information is extracted from the ATM adaptation layer service data unit. In the preferred embodiment  
15 of the invention, the flow control information is inserted into the user data field of the ATM adaptation layer service data unit. The in-channel signalling approach is a very flexible and simple way to arrange the tunnelling of the flow control information. In the out-channel signalling approach, some modification in the signalling messages may be required, depending on the signalling system used.  
20

### **Brief Description of the Drawings**

The invention will now be described by means of preferred embodiments with reference to the attached drawings, in which

Figure 1 shows a simplified UMTS architecture,

25 Figure 2 illustrates the protocol stacks which may be used in a pure third generation mobile system,

Figure 3 shows protocol stacks which may be used in a mixed 3G and 2G mobile system,

### **Preferred Embodiments of the Invention**

30 The preferred embodiments of the invention are described in the following as implemented in the third generation mobile system when the transport network is an ATM network. However, the aim is not to restrict the invention to these embodiments. The invention is applicable to be used in any telecommunications system in which an intermediate connection leg fails to

support any lower level flow control mechanism while such a flow control mechanism is supported by the connection legs or equipment to which the intermediate leg is connected to. As used herein, the term leg may also refer to a user interface between a node and user equipment or application connected thereto.

The architecture of the UMTS access network was described above with reference to Figure 1, and examples of the protocol stacks were illustrated in Figures 2 and 3.

With reference to Figures 2 and 3, the relay layer in the RNC and in the 3GMSC or the IWU illustrates any high-layer protocols or entities required. In the UTRAN reference model as well as in the ATM reference model, these higher layers are defined to include a user plane and the control plane. In the UTRAN the control plane is further divided into a radio network control plane and a transport network control plane for radio network control and signalling. The transport network control plane is designed for the ATM based transport network in the interface Iu. Both the standardized ATM connection control signalling (PNNI, UNI, BISUP) and AAL2/AAL5 signalling protocol are available. The user (the protocol entity) in the user or control plane has an access to the underlying ATM adaptation layer, or even to the ATM layer, through an ATM adaptation layer service access point (AAL/SAP) both in the RNC and in the 3GMSC (Figure 2) or the IWU (Figure 3). Thereby, the AAL service provides a capability to transfer ATM adaptation layer service data units (AAL-SDU) from one AAL-SAP to one other AAL-SAP in the interface Iu through the ATM network. In the RNC the same user entity or a user entity it co-operates with has access to a RLC entity in the RNC-MS leg. In the 3GMSC the AAL-SAP user is the LAC and/or the interworking function on the relay level. The interworking function has access to a protocol employed on the lower transmission protocol level in a fixed network, such as V.120. Also in the IWU the AAL-SAP user is the LAC and/or the interworking function on the relay level. The interworking function has access to an entity in the lower level GSM protocol, such as RLP or RA (rate adaption), employed in the IWU-MSC leg in Figure 3. In the 2GMSC the relay layer provides standard interworking between the GSM protocols and the fixed network protocols.

As noted above, the ATM leg does not support a flow control mechanism which would assure the data integrity. Therefore, in accordance with the present invention, the higher layer entities in the RNC, the 3GMSC

and the IWU are provided with the capability to recognize a need for flow control in the ATM leg and to tunnel the associated flow control information over the ATM leg to the high level entity at the transmitting end. The transmitting entity is arranged to implement the flow control in the ATM leg on the basis of the tunnelled information.

The flow control mechanism may be a mechanism using Flow Control ON/Flow Control OFF type of flow control. In this case, when the flow control is set ON by the receiving network element on one side of the tunnel, e.g. in the RNC, the transmitting network element, e.g. the MSC, on the other side of the tunnel sends no data until flow control is set OFF. Alternatively, a dynamic flow control mechanism may be used. In this mechanism, the RNC tells the MSC to reduce the data rate when the need for flow control is recognized. For example, the data rate may be reduced to 75 %, 50 %, 25 % or 0 % of the nominal data rate of the connection. In the following, the preferred embodiments are described with the ON/OFF mechanism, but alternatively the dynamic flow control can be used in these embodiments.

The first embodiment of the invention in which the tunnelling is implemented by in-channel signalling will now be described.

Let us assume that data is transmitted from the mobile station MS to the 3GMSC and further to the fixed network in the system of Figure 2. A RLC/MAC link with flow control is established between the MS and RNC. An ATM connection is established between the RNC and the 3GMSC. An LAC protocol link is established between the MS and the 3GMSC. A fixed network traffic channel using V.120 protocol is established between the 3GMSC and the other party in the fixed network.

The need for the flow control is recognized by the user of the AAL-SAP in the RNC or the 3GMSC. The need for the flow control can be recognized, for example, from the lower layer receiving or transmitting buffer status in the ATM leg or from the flow control request incoming from the following leg in the downlink, i.e. from the mobile station MS to the RNC or from the PSTN/ISDN to the MSC or IWU. According to the in-channel signalling approach of the present invention, a flow control request is provided by the user of the AAL-SAP upon detecting the need to activate or deactivate the flow control towards the ATM leg. The flow control request is packed into the AAL-SDU, preferably into the payload part of it. In the preferred embodiment of the invention the packing is performed in the service-specific convergence sub-

layer (SSCS) which is the uppermost sub-layer in the AAL layer and can be modified in this respect. The user of the AAL-SAP is arranged to, via the AAL-SAP, to command the SSCS to send the flow control ON request or the flow control OFF request, depending whether the flow control is to be activated or deactivated. Alternatively, the flow control information may be added to the user data prior to inputting the user data to the AAL layer in which case the user information will be inherently packed into the AAL-SDU. The AAL-SDU is transported through the AAL lower layers and the ATM layer to the other end of the ATM connection (e.g. from the RNC to the MSC or vice versa) as specified in the ATM specifications. The receiving AAL-SAP user or the SSCS sub-layer extracts the flow control information from the received AAL-SDU. The received flow control information is used to implement the flow control. This may include mapping or converting the flow control information into the flow control request according to the previous leg (e.g. the MS-RNC or the MSC-fixed network) in order to activate or deactivate the flow control towards the previous leg. The implementation of the flow control may also include adapting the AAL-SAP user's own operations to the status of the flow control indicated by the received flow control information, e.g. stopping the sending of new data if the flow control request indicates that the flow control is active (ON), and restarting the sending of new data if the flow control request indicates that the flow control is deactivated (OFF).

There are several alternative ways for packing the flow control information into the AAL-SDU.

1) An octet carrying the flow control request (ON or OFF) is always inserted in the AAL-SDU, for example before the first user data octet. A receiving entity will always know that the first payload octet contains flow control information (and perhaps some other status/control information). This is applicable to all AAL types, i.e. AAL1, AAL2 and AAL5.

2) A bit or bits carrying the flow control request (ON or OFF) is/are always inserted in the AAL-SDU, for example before the first user data bits. The receiving entity will always know that the first payload bit(s) contain(s) flow control information (and perhaps some other non-user-data information). This is applicable to AAL type 1 operating in the non-structured mode, for example.

3) An octet or (a) bit(s) carrying the flow control information (and/or other status/control information) is inserted in the AAL-SDU as the only payload information, or with only a limited amount of user data in the payload, in

order to make the whole payload fit in one or a limited number of ATM cells. In this way the flow control (and/or status/control) information must not be presented in all AAL-SDUs, but the flow control request is transmitted only when required. The AAL-SDUs carrying the flow control information is in a normal manner provided with a length indication, e.g. a length indicator in the AAL2 and AAL5, or a sequence number in the AAL1. The receiver is able to identify the AAL-SDUs carrying the flow control information by means of this length indication. A short AAL-SDU is carrying flow control and/or status/control information, whereas longer AAL-SDUs are carrying pure user data. This method is applicable to all AAL types.

In the octet based transmission (e.g. AAL5, AAL2) a whole octet is used to carry the flow control (and/or status/control) information, which means that the information can be protected by an error correcting code. This is useful in a service, such as AAL5, which allows corrupted SDUs to be delivered to the service user.

In one embodiment of the invention the user or control plane has access to the ATM layer. The flow control information is transmitted from/to the user or control plane to/from the ATM layer with interlayer primitives or messages. The ATM layer transports the flow control information to the peer ATM layer in an ATM cell. In addition to the flow control information, the cell will carry a connection identifier and cell or payload type identifier in order to enable the receiving ATM entity to deliver the information to the correct user or control entity.

There are several ways how an ATM cell can carry the required information, for example:

- The payload type of an ATM cell is given a dedicated value, e.g. "Connection related information" or "Flow control information". The VPI and VCI fields of the cell are used for the connection identifier (as usual in the ATM). The information field of the cell is used for carrying additional information, e.g. Flow Control ON, Flow Control OFF.

- The payload type of an ATM cell is given a value "user data". The VPI and VCI fields of the cell are given a dedicated value, e.g. "Connection related information" or "Flow control information" or "Signalling information". The information field of the cell is used for carrying the connection identification and additional information, e.g. Flow Control ON, Flow Control OFF.

According to the second aspect of the invention, the flow control information is tunnelled over the ATM leg in out-channel signalling, i.e. using a control plane message.

The user plane protocol entity in the RNC, i.e. MAC/RLC user entity, or in the MSC, i.e. a fixed network protocol user entity, or in the IWU, i.e. a GSM protocol user entity, recognizes the need for flow control towards the ATM leg of the connection. The recognition may be based on the buffer status or the flow control information received, for example. The user plane protocol entity then indicates the need of the flow control to the call control and signalling entity in the control plane, e.g. by sending a "flow control required in this connection" message with parameters identifying the connection or channel in question.

The control plane sends the flow control request in an out-of-band signalling message associated with the connection to the peer signalling entity behind the ATM connection. In other words, the RNC sends a message to the MSC or the IWU, and the MSC or the IWU sends a message to the RNC. The type or format of the message depends on the signalling system used.

If the ATM user-to-network interface signalling (UNI) is employed, a connection related STATUS message can be used, for example. Only new status parameters values, such as "flow control ON" and "flow control OFF", are defined in the STATUS message. The UNI is defined in the ITU-T Q.2931 which also defines the STATUS message. There are unused parameters values in the STATUS message according to the Q.2931 which can be used for the purpose of the invention.

If the ATM network to network interface signalling (NNI) according to the recommendation ITU-T Q.2763 is used, the user to user signalling (UUS) message, for example, can be used for carrying the flow control information according to the invention.

If another kind of signalling, such as RAN-MAP, is used, a corresponding connection associated message can be employed to transport a flow control ON/OFF request to the peer signalling or call control entity. Because the RAN-MAP is currently under specification, it is easy to specify flow control parameters for a message or even a dedicated message for this purpose. The receiving signalling and call control entity extracts the flow control request from the received signalling message and forwards it to the relevant user plane control entity. The user plane control entity employs the flow control request

for implementation of the flow control. For example, the user plane control entity may map the flow control request to the flow control mechanism of the protocol of the previous traffic channel leg, e.g. to the MAC/RLC in the RNC, or to the GSMRLP or GSMRA in the IWU, or to the ISDN V.120 in the MSC, in  
5 order to thereby activate or deactivate the flow control towards the previous leg.

The invention was described above in embodiments using circuit-switched connections. However, the invention can also be applied in conjunction with packet data services.

10 The invention should not be limited to the specific examples described herein. Rather, the spirit and the scope of the invention should be construed in accordance with the claims attached hereto.



**Claims**

1. A data transmission method in a telecommunications system, comprising a step of

transmitting data over a connection comprising a first leg supporting  
5 flow control on a lower transmission protocol level underlying a user level, an intermediate second leg not supporting flow control on the lower transmission level, and a third leg supporting flow control on the lower transmission protocol level,

characterized by further steps of  
10 tunnelling lower level flow control information transparently over the lower transmission protocol level of the second leg between said first and third legs in order to provide end-to-end flow control and thereby data integrity over the connection on the lower transmission protocol layer.

2. The method as claimed in claim 1, characterized by  
15 tunnelling said flow control information as in-channel signalling over the second leg.

3. The method as claimed in claim 1 or 2, characterized in that said second leg is an ATM connection, and that said lower transmission protocol level includes an ATM adaptation layer.

20 4. The method as claimed in claim 3, characterized by encapsulating the flow control information in an ATM adaptation layer service data unit,

transporting the ATM adaptation layer service data unit to the other end of the second leg in accordance with an ATM network protocol,

25 extracting the flow control information from the ATM adaptation layer service data unit at said other end of the second leg.

5. The method as claimed in claim 3 or 4, characterized by inserting the flow control information in the ATM adaptation layer service data unit in one of the following ways:

30 inserting an octet carrying the flow control information before a first user data octet in a payload field of the ATM adaptation layer service data unit, inserting a bit or bits carrying the flow control information before first user data bits in a payload field of the ATM adaptation layer service data unit,

inserting an octet or a bit or bits carrying the flow control information  
35 in the ATM adaptation layer service data unit as the only payload information in the payload field, or

inserting an octet or a bit or bits carrying the flow control information with a limited amount of user data in the payload of the ATM adaptation layer service data unit.

6. The method as claimed in claim 1, 2 or 3, characterized  
ε by

said second leg being an ATM connection  
tunnelling said flow control information in ATM cells in an ATM layer over the ATM connection.

7. The method as claimed in claim 1 or 3, characterized by  
10 tunnelling said flow control information over the second leg in an out-of-traffic-channel signalling associated with a connection.

8. The method as claimed in any one of claims 1-7, characterized by said step of tunnelling comprising further steps of  
recognizing at a first node between the first and second legs a need  
15 to start a flow control towards the second leg,  
sending a flow control ON request over the second leg,  
receiving the flow control ON request at a second node between the second and third legs,  
stopping sending new data or decreasing data rate from the second  
20 node to the first node over the second leg in response to the flow control ON request.

9. The method as claimed in claim 8, characterized by said step of tunnelling comprising further steps of  
recognizing at the first node a need of stopping the flow control to-  
25 wards the second leg,  
sending a flow control OFF request over the second leg,  
receiving the flow control OFF request at the second node,  
starting sending new data or increasing data rate from the second node to the first over the second leg in response to said flow control off request.  
30

10. The method as claimed in any one of claims 1-9, characterized by said step of tunnelling comprising further steps of  
recognizing at a first node between the first and second legs a need to start flow control towards the second leg,  
35 sending a flow control ON request over the second leg,

receiving the flow control ON request at a second node between the second and third legs,

activating in the second node flow control towards the third leg in response to the flow control ON request.

5           11. The method as claimed in any one of claims 1-10, characterized by said step of tunnelling comprising further steps of recognizing at the first node a need of stopping the flow control towards the second leg,

          sending a flow control OFF request over the second leg,  
10           receiving the flow control OFF request at the second node, deactivating in the second node flow control towards the third leg in response to the flow control ON request.

          12. The method according to any one of claims 1-11, characterized by  
15           recognizing the need for starting or stopping the flow control being based on the status of a receiving or transmitting buffer in the first node or on incoming flow control information received over the first leg.

          13. A telecommunications system, comprising  
          a first connection leg supporting flow control on a lower transmission protocol level underlying a user level,  
20           an intermediate second connection leg not supporting flow control the lower transmission level,  
          a third connection leg supporting flow control on the lower transmission protocol level,

25           a first node between the first and second legs,  
          a second node between the second and third legs,  
          characterized in that the first and second nodes are arranged to tunnel lower level flow control information transparently over the lower transmission protocol level of the second leg between said first and third  
30           legs in order to provide end-to-end flow control and thereby data integrity over the connection on the lower transmission protocol layer.

          14. The system as claimed in claim 13, characterized in that the first and second nodes are arranged to tunnel said flow control information in in-channel signalling over the second leg.

15. The system as claimed in claim 13 or 14, characterized in that said second leg is an ATM connection, and that said lower transmission protocol level includes an ATM adaptation layer.

16 The system as claimed in claim 15, characterized in that  
5 said first and second nodes are arranged to insert the flow control information in an ATM adaptation layer service data unit.

17. The system as claimed in claim 14 or 15, characterized  
in that said second leg is an ATM connection, and that said first and second  
nodes are arranged to tunnel the flow control information in ATM cells in an  
10 ATM layer over the ATM connection.

18. The system as claimed in any one of claims 13 or 15, characterized in that the first and second nodes are arranged to tunnel said flow control information in out-of-traffic-channel signalling over the second leg.

19. The system as claimed in any one of claims 13-18, characterized  
15 in that the first and second nodes are arranged to recognize a need to start or stop flow control towards the second leg and to send a flow control ON request or a flow control OFF request, respectively, over the second leg, and the first and second peer entities are responsive to receiving the flow control ON request or the flow control OFF request for stopping or starting, respectively,  
20 the sending, or decreasing and increasing data rate, respectively, of data towards the second leg,

20. The system as claimed in any one of claims 13-19, characterized in that the first and second nodes are arranged to recognize a need to start or stop flow control towards the second leg and to send a flow  
25 control ON request or a flow control OFF request, respectively, over the second leg, and the first and second peer entities are responsive to receiving the flow control ON request or the flow control OFF request for activating or deactivating, respectively, flow control towards the first or the third leg.

21. The system as claimed in any one of claims 13-20, characterized  
30 in that the recognition of the need for starting or stopping the flow control based on the status of a receiving or transmitting buffer in the nodes or on incoming flow control information received over the first or the third leg.

22. The system as claimed in any one of claims 13-21, characterized  
35 in that the system is a mobile communications system, and that the first and second nodes are network elements of the mobile communication system.

tions system, and that the first leg is at the air interface between a mobile station and one of said network elements.

1/1

Fig. 1





Fig. 2




Fig. 3

# INTERNATIONAL SEARCH REPORT

International application No.

PCT/FI 00/00025

## A. CLASSIFICATION OF SUBJECT MATTER

IPC7: H04Q 7/24, H04Q 11/04

According to International Patent Classification (IPC) or to both national classification and IPC

## B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC7: H04Q, H04L

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

SE,DK,FI,NO classes as above

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

## C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	WO 99/19999 A1 (ERICSSON INC.), 22 April 1999 (22.04.99) --	1-22
A	WO 99/33319 A1 (TELEFONAKTIEBOLAGET LM ERICSSON (PUBL)), 1 July 1999 (01.07.99) --	1-22
A	WO 97/34392 A1 (TELEFONAKTIEBOLAGET LM ERICSSON (PUBL)), 18 Sept 1997 (18.09.97) --	1-22
A	EP 0798943 A2 (YRP MOBILE TELECOMMUNICATION KEY TECHNOLOGY RESEARCH LABORATORIES CO., LTD.), 1 October 1997 (01.10.97) --	1-22

☒ Further documents are listed in the continuation of Box C.

☒ See patent family annex.

* Special categories of cited documents:	"I" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"A" document defining the general state of the art which is not considered to be of particular relevance	"X" document of particular relevance: the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"E" earlier document but published on or after the international filing date	"Y" document of particular relevance: the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
"I" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)	"&" document member of the same patent family
"O" document referring to an oral disclosure, use, exhibition or other means	
"P" document published prior to the international filing date but later than the priority date claimed	

Date of the actual completion of the international search

15 June 2000

Date of mailing of the international search report

20-06-2000

Name and mailing address of the ISA/

Swedish Patent Office  
Box 5055, S-102 42 STOCKHOLM  
Facsimile No. +46 8 666 02 86

Authorized officer

MÅNS MARKLUND/EE  
Telephone No. +46 8 782 25 00

# INTERNATIONAL SEARCH REPORT

International application No.

PCT/FI 00/00025

C (Continuation). DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	<p>WO 97/25824 A1 (NOKIA TELECOMMUNICATIONS OY), 17 July 1997 (17.07.97)</p> <p style="text-align: center;">-- -----</p>	1-22



# INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No.

PCT/FI 00/00025

Patent document cited in search report			Publication date	Patent family member(s)	Publication date
WO	99/19999	A1	22/04/99	NONE	
WO	99/33319	A1	01/07/99	NONE	
WO	97/34392	A1	18/09/97	NONE	
EP	0798943	A2	01/10/97	AU 672865 B	17/10/96
				AU 5716394 A	19/07/94
				CH 685701 A	15/09/95
				DE 4396846 T	26/01/95
				EP 0628050 A,B	14/12/94
				GB 2279650 A,B	11/01/95
				GB 9416016 D	00/00/00
				JP 2853026 B	03/02/99
				JP 8502999 T	02/04/96
				JP 9261713 A	03/10/97
				SE 9402735 A	16/08/94
				US 5679787 A	21/10/97
				US 5877311 A	02/03/99
				JP 2945341 B	06/09/99
				JP 10224375 A	21/08/98
WO	97/25824	A1	17/07/97	NONE	

## PCT REQUEST

2990008PC/su

Original (for SUBMISSION) - printed on 14.01.2000 01:07:45 PM

0 0-1	For receiving Office use only International Application No.	PCT/FI 00 / 0 0 0 2 5
0-2	International Filing Date	14 JAN 2000 (14.01.00)
0-3	Name of receiving Office and "PCT International Application"	The Finnish Patent Office PCT International Application
0-4 0-4-1	Form - PCT/RO/101 PCT Request Prepared using	PCT-EASY Version 2.90 (updated 15.12.1999)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	National Board of Patents and Registration (Finland) (RO/FI)
0-7	Applicant's or agent's file reference	2990008PC/su
I	Title of invention	FLOW CONTROL METHOD IN A TELECOMMUNICATIONS SYSTEM
II II-1 II-2 II-4 II-5	Applicant This person is: Applicant for Name Address:	applicant only all designated States except US NOKIA NETWORKS OY Keilalahdentie 4 FIN-02150 Espoo Finland
II-6	State of nationality	FI
II-7	State of residence	FI
III-1 III-1-1 III-1-2 III-1-4 III-1-5	Applicant and/or inventor This person is: Applicant for Name (LAST, First) Address:	applicant and inventor US only RÄSÄNEN, Juha Pensaskertuntie 8 A FIN-02660 Espoo Finland
III-1-6	State of nationality	FI
III-1-7	State of residence	FI

## PCT REQUEST

2990008PC/su

Original (for SUBMISSION) - printed on 14.01.2000 01:07:45 PM

III-2	<b>Applicant and/or inventor</b>	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	OHVO, Mikko
III-2-5	Address:	Johanbergintie 102 FIN-04660 Numminen Finland
III-2-6	State of nationality	FI
III-2-7	State of residence	FI
IV-1	<b>Agent or common representative; or address for correspondence</b> The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	KOLSTER OY AB
IV-1-2	Address:	Iso Roobertinkatu 23 P.O. Box 148 FIN-00121 Helsinki Finland
IV-1-3	Telephone No.	+ 358 9 618 821
IV-1-4	Facsimile No.	+ 358 9 602 244
IV-1-5	e-mail	Kolster@Kolster.Fi
V	<b>Designation of States</b>	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW SD SL SZ TZ UG ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE CH&LI CY DE DK ES FI FR GB GR IE IT LU MC NL PT SE and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT

## PCT REQUEST

2990008PC/su


Original (for SUBMISSION) - printed on 14.01.2000 01:07:45 PM

V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AL AM AT (patent and utility model) AU AZ BA BB BG BR BY CA CH&LI CN CR CU CZ (patent and utility model) DE (patent and utility model) DK (patent and utility model) DM EE (patent and utility model) ES FI (patent and utility model) GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR (patent and utility model) KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX NO NZ PL PT RO RU SD SE SG SI SK (patent and utility model) SL TJ TM TR TT TZ UA UG US UZ VN YU ZA ZW	
V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations	NONE	
VI-1	Priority claim of earlier national application		
VI-1-1	Filing date	15 January 1999 (15.01.1999)	
VI-1-2	Number	990071	
VI-1-3	Country	FI	
VI-2	Priority document request The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):	VI-1	
VII-1	International Searching Authority Chosen	Swedish Patent Office (ISA/SE)	
VIII	Check list	number of sheets	electronic file(s) attached
VIII-1	Request	4	-
VIII-2	Description	13	-
VIII-3	Claims	5	-
VIII-4	Abstract	1	2990008p.txt
VIII-5	Drawings	1	-
VIII-7	TOTAL	24	
	Accompanying items	paper document(s) attached	electronic file(s) attached
VIII-8	Fee calculation sheet	✓	-
VIII-10	Copy of general power of attorney	✓	-
VIII-16	PCT-EASY diskette	-	diskette
VIII-17	Other (specified):	Copy of Official Action	-

## PCT REQUEST

2990008PC/su

Original (for SUBMISSION) - printed on 14.01.2000 01:07:45 PM

VIII-18	Figure of the drawings which should accompany the abstract	2
VIII-19	Language of filing of the international application	English
IX-1	Signature of applicant or agent	
IX-1-1	Name	KOLSTER OY AB Tapio Valkeiskangas

## FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	14 JAN 2000 (14 -01- 2000 )
10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/SE
10-6	Transmittal of search copy delayed until search fee is paid	

## FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

REC'D 09 MAR 2001

REPORT  
WIPO

PCT

Applicant's or agent's file reference 2990008PC/su	<b>FOR FURTHER ACTION</b> See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/FI00/00025	International filing date ( <i>day month year</i> ) 14.01.2000	Priority date ( <i>day month year</i> ) 15.01.1999
International Patent Classification (IPC) or national classification and IPC7 H04Q 7/24, H04Q 11/04		
Applicant Nokia Networks OY et al.		

<p>1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.</p> <p>2. This REPORT consists of a total of <u>4</u> sheets, including this cover sheet.</p> <p><input type="checkbox"/> This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).</p> <p>These annexes consist of a total of _____ sheets.</p>	
<p>3. This report contains indications relating to the following items:</p> <p>I <input checked="" type="checkbox"/> Basis of the report</p> <p>II <input type="checkbox"/> Priority</p> <p>III <input type="checkbox"/> Non-establishment of opinion with regard to novelty, inventive step and industrial applicability</p> <p>IV <input type="checkbox"/> Lack of unity of invention</p> <p>V <input checked="" type="checkbox"/> Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement</p> <p>VI <input type="checkbox"/> Certain documents cited</p> <p>VII <input type="checkbox"/> Certain defects in the international application</p> <p>VIII <input type="checkbox"/> Certain observations on the international application</p>	

Date of submission of the demand  04.08.2000	Date of completion of this report  16.01.2001
Name and mailing address of the IPEA/SE Patent- och registreringsverket Box 5055 S-102 42 STOCKHOLM Facsimile No. 08-667 72 88	Authorized officer  Kristoffer Ogebjer/LR Telephone No. 08-782 25 00

**I. Basis of the report****1. With regard to the elements of the international application:\***

- ☒ the international application as originally filed
- ☐ the description:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_
- ☐ the claims:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, as amended (together with any statement) under article 19  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_
- ☐ the drawings:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_
- ☐ the sequence listing part of the description:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_

**2. With regard to the language, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.**

These elements were available or furnished to this Authority in the following language \_\_\_\_\_ which is:

- ☐ the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

**3. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:**

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

**4. ☐ The amendments have resulted in the cancellation of:**

- ☐ the description, pages \_\_\_\_\_
- ☐ the claims, Nos. \_\_\_\_\_
- ☐ the drawings, sheet/fig \_\_\_\_\_

**5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2 (e)).\*\***

\* Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).

\*\* Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.

## INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.  
PCT/FI00/00025

## V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

## 1. Statement

Novelty (N)	Claims	<u>1-22</u>	YES
	Claims		NO
Inventive step (IS)	Claims	<u>1-22</u>	YES
	Claims		NO
Industrial applicability (IA)	Claims	<u>1-22</u>	YES
	Claims		NO

## 2. Citations and explanations (Rule 70.7)

The claimed invention relates to flow control in data transmission in telecommunications systems. The connection comprises three legs, where two legs, first and third, support flow control on the lower transmission protocol level and the second leg does not support flow control. By tunnelling lower level flow-control information transparently over the lower transmission protocol level of the second leg between the first and third leg the transmission of new data on the lower transmission protocol level is ceased. /restarted or the data rate decreased/increased when the flow control information activates/deactivates the flow control in the transmitting node.

Cited documents in search reports:

D1: WO, A2, 9919999  
D2: WO, A2, 9933319  
D3: WO, A2, 9745978  
D4: EP, A2, 0798943  
D5: WO, A1, 9734392

D1 discloses a system where control information is sent by tunnelling signalling messages between the remote terminal and the network. The system does not involve "lower layer" transmission.

D2 presents an ATM platform. Signalling and traffic communications between the function modules are effected asynchronously to efficiently meet current service data rate demands using the ATM switch and ATM switching protocol.

.../...



**Supplemental Box**

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: V

D3 discloses flow control in data transmission in telecommunications systems. QFC in the lower layer guarantees a low loss service.

From what the documents cited above show, the invention, according to claims 1-22, differs in the matter of tunnelling lower level flow-control information transparently over the lower transmission protocol level of the second leg between the first and third leg. This is considered not to be obvious for a person skilled in the art and therefore considered to involve an inventive step.

D4, D5 present flow-control to mobile communication networks by buffering incoming cells.